



PSE&G ELECTRIC RELIABILITY UPGRADE PROJECT MONTGOMERY TOWNSHIP, NEW JERSEY

QUESTIONS & ANSWERS

1. WHY IS PSE&G IMPROVING UTILITY LINES?

PSE&G is currently upgrading the electric power supply in Montgomery Township to meet the increased demand for power, as well as provide improved electric reliability to our customers. Since 1990, Montgomery Township's population has grown 140 percent. Since 2000, there has been a 22 percent increase in residential and commercial electric demand.

In addition, this project is designed to improve electric reliability to our customers by reducing the number of outages customers may experience. Currently, the Montgomery area experiences approximately ten outages per year.

2. WAS THE TOWNSHIP PROVIDED NOTICE OF THIS PROJECT?

PSE&G notified Montgomery Township of this project in October 2009.

3. WHO GAVE PSE&G APPROVAL TO INSTALL UTILITY POLES?

Utility companies in New Jersey cannot install utility poles on private property without a property owner's approval. Utility companies have a legal right, however, to occupy the public right-of-way with electric and gas facilities without obtaining state or local approval.

5. WHAT IS THE HEIGHT OF THE EXISTING UTILITY POLES? WHAT IS THE HEIGHT OF THE REPLACEMENT POLES?

In general, the existing poles stand approximately 40 - 55 feet in height. The replacement poles will range in height between 55 and 60 feet, approximately 0 to 20 feet higher than the existing poles.

6. WHY DO THE REPLACEMENT POLES APPEAR TWICE AS HIGH AS THE OLD POLES?

Once a replacement pole is installed and the electric wires are transferred, the old pole is cut to the height of the lowest telephone and/or cable television line that shares the pole. At this time, the public is viewing the replacement pole adjacent to the old pole which has been cut to a height of approximately 20 – 25 ft above grade.

7. WHY ARE THE REPLACEMENT POLES TALLER?

The height of a utility pole is determined by several factors: 1) the number of wires carried by the pole – the more wire, the taller the pole; 2) the distance between poles - the greater the distance the taller the poles; 3) the voltage of the wires - different voltages require different spacing of the wires; and, 4) the addition of static wire – lightning protection.

8. WHAT IS THE DIFFERENCE BETWEEN THE EXISTING AND NEW LINE VOLTAGE?

Existing pole lines in Montgomery Township carry 13 kV and/or 26 kV lines. The new pole line will carry the existing lines as well as a new 69 kV line.



10. HOW DID PSE&G DETERMINE THE LOCATION OF THE REPLACEMENT POLE LINE?

PSE&G considers several factors as part of its pole line selection process. Such factors include but are not limited to: presence or absence of existing utilities, feasibility of engineering and/or construction, use of public and private properties, environmental and cultural impacts and approvals, cost and schedule to construct, and feasibility of long term maintenance and accessibility.

11. WHAT OTHER ROUTE ALTERNATIVES ARE AVAILABLE?

Based upon electric system design specifications and configuration, the location of existing facilities, and the environmental and cultural constraints, no other alternate route exists to accomplish the project goals without the use of private property and/or the installation of an entirely new pole line.

12. DID PSE&G CONSIDER ENVIRONMENTAL ISSUES WHEN PLANNING THIS PROJECT?

Yes. In accordance with New Jersey Department of Environmental Protection (NJDEP) regulations, PSE&G evaluated the potential impact to environmental media including land, wetlands, waterways, and wildlife. A project notification will be transmitted to NJDEP Division of Land Use Regulation and the NJDEP Bureau of Coastal and Land Use Compliance and Enforcement.

13. WILL THE CONSTRUCTION DISRUPT TRAFFIC?

PSE&G is required to maintain traffic control measures, including assistance from local police personnel, when working in the public right-of-way.

14. WHAT HEALTH HAZARDS ARE ASSOCIATED WITH THESE LINES?

Wherever electric service is available, pole lines carrying voltages of 13kV, 26kV and/or 69 kV typically exist and such pole lines occur on almost every roadway in New Jersey, as well as North America. No documented evidence exists that correlates health hazards to utility pole lines.

15. WHAT ARE THE CONCERNS FOR FIREMAN WHO RESPOND TO DOWNED ELECTRIC WIRE OR TRANSFORMER FIRES?

Fire fighters who respond to this type of situation know not to handle downed electric wire and/or extinguish transformer fires. Fire fighters and police personnel will secure the area, maintain crowd & traffic control and await response by PSE&G. The hazards are therefore limited to those they may encounter at any other fire.

PSE&G will continue to provide updates to Montgomery Township on the pole line the relocation effort as information becomes available. In the meantime, should you have additional questions or concerns about this project, please contact PSE&G's Electric Reliability Upgrade number at 856-778-6983. All calls will be returned within 24 hours during normal business days.